

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 IN 1990 AT A MEETING HELD ON 1-10-94  
AL RINGENBERG, CO. REP.

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'94 DEC 14 AM 11 58

*Julie VanZandt*  
REG. OF DEEDS

or corners in

HILLSDALE  
(County)

Located In:

Corner Code #1

Public Land Survey

T 5S R 1W  
T R  
T R  
T R

C-3, C-5

SURVEY &  
REMONUMENTATION

Property Controlling  
in Section

S T R  
S T R

APR 27 1995

Register of Deeds Stamp & File Number

Miscellaneous

S T R

COMMISSION

Property in Sec.

S T R

Lot No. Recorded Plat

Private Claims

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		●										
4	7	●	8	9	10	11	12					
5		●										
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John E. Maxson, in a field survey on 4 November, 1994

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-3  
GLO, 1824, 16"B.Oak, N62W, 26 lks  
7"B.Oak, S13W, 1.04 lks  
Co. Sur 1891, Stone  
18"W.Oak, S84W, 6 lks  
LCRC, 1976, Ringenberg, L1, P558  
Stone  
VanGieson Survey, 1986, L558, PB48  
Anchor Post

C-4  
GLO, 1824, 10"B.Oak, N59W, 6 lks  
6"B.Oak, S84W, 3 lks  
LCRC, 1976, Ringenberg, L1, P558  
1/2" Iron  
VanGieson Survey, 1980, L1, P667  
1/2" Iron

C-5  
GLO, 1824, 16"B.Oak, N62W, 26 lks  
7"W.Oak, S13W, 1.04 lks  
LCRC, 1976, Ringenberg, L1, P558  
1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-3  
Found stone next to fence Post  
from Ringenberg LCRC and accepted  
as the best available evidence of  
the position of the original Corner

C-4  
Found concrete monument  
at fence intersection and accepted  
as the best available evidence of  
the position of the original Corner

C-5  
Found iron from Ringenberg LCRC  
with many flat stones under it and  
accepted as the best available  
evidence of the position of the  
original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-3  
Reset 5/8 x 36 rebar w/cap  
N68W 15.16' 18"Oak  
N55E 21.92' 12"Oak  
S35E 24.96' 12"Oak  
S57W 32.22' 12"Oak

C-4  
Reset 5/8 x 36 rebar w/cap  
N05E 14.63' 8"Locust  
N45E 41.21' 12"Cherry  
S60W 2.46' 6"Ash  
S85W 34.98' 8"Locust

C-5  
Reset 5/8 x 36 rebar w/cap  
N84W 32.08' 40"Oak  
N50E 33.80' 16"Cherry  
S10E 21.58' 36"Oak  
N75E 38.48' 8"Oak

Signed by *John E. Maxson*  
Surveyor's Michigan License No. 27454

Date 12 December, 1994

