

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1900 AT A MEETING HELD ON 11-10-94 AL RINGENBERG CO. REP.

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 '94 DEC 14 AM 11 58

For corners in

HILLSDALE (County) Located In: Corner Code #
 1. Public Land Survey T 5S R1W (D1) D3, D5
 T R
 T R
 T R
 2. Property Controlling S T R
 In Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 4. Lot No. , Recorded Plat
 5. Private Claims

Judy VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John E. Maxson, in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 GLO did not set this corner Ringenberg Survey, 1978, L1, P596 1/2" Iron VanGieson Survey, 1987, L558, P848	D-3 GLO, 1824, 24"W.Oak, N81W, 34 lks 7"W.Oak, S32E, 1.08 lks Ringenberg Survey, 1978, L1, P596 VanGieson Survey, 1987, L558, P848 3/4" Pipe	D-5 GLO, 1824, 20"W.Oak, S17E, 1.18 lks 6"W.Oak, S87E, 60 lks LCRC, 1978, Ringenberg, L1, P559 Steel Fence Post
--	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found iron from Recorded Surveys and accepted as the best available evidence of the position of the original Corner	D-3 Found iron from Recorded Surveys with 1 1/2" pipe below and accepted as the best available evidence of the position of the original Corner	D-5 Found post from Ringenberg LCRC and accepted as the best available evidence of the position of the original Corner
--	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Reset 5/8 x 36 rebar w/cap S46E 41.65' 36"Walnut S45W 39.46' 36"Walnut N32W 34.69' 18"Walnut N05W 24.62' 12"Walnut West 137.23' Con .Mon. D-13, T4S-R1W	D-3 Reset 5/8 x 36 rebar w/cap N25E 44.40' 20"Hickory S47W 50.22' 12"Oak S60W 43.82' 36"Tw.Oak N48W 51.51' 24"Tw.Oak	D-5 Reset 5/8 x 36 rebar w/cap N50W 20.37' 10"Maple N65E 49.67' 16"Hickory N62W 17.55' 10"Maple S34E 32.67' 20"Maple
--	---	---

Signed by John E. Maxson Date 12 December, 1994
 Surveyor's Michigan License No. 27454

