

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 1980 AT A MEETING HELD ON 10-24-94  
 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 84  
 REMONUMENTATION

97922

RECORDED  
 HILLSDALE CO. MICH.

'94 DEC 14 AM 11 59

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt  
 REG. OF DEEDS

For corners in

HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey	T 5S R 1W	E3.
	T R	
	T R	
	T R	
2.. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY &  
 REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John E. Maxson, in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- E-3  
GLO, 1824, 6" Tamarack, S24W, 2.97 lks  
18" B. Oak, N03E, 10.9 lks
- Ringenberg Survey, 1978, L1, P596  
Cor. in Lake
- VanGieson Survey, 1987, L558, P848  
Cor. in Lake

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3  
This corner is now under water.  
Reestablished position from the Plat of "LAKEVIEW NO. 1" as the best available position of the original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-3  
In water, no monument set  
N00°28'43"E 2636.62' Ref. Mon. #1  
5/8" Rebar w/cap  
E-2, T5S-R1W  
S89°21'43"W 2673.92' Ref. Mon. #2  
5/8" Rebar w/cap  
D-3, T5S-R1W  
S00°05'10"W 1020.97' Ref. Mon. #3  
Con. Plat Mon.
- Witnesses to Ref. Mon #3  
Con. Plat Mon. at SW Cor. Lot #96  
South 4.48' 48" Willow  
N10W 8.65' 14" Oak  
North 5.20' Con. Mon.

Signed by John E. Maxson  
 Surveyor's Michigan License No. 27454

Date 12 December 1994

