

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-10-94 AL RINGENBERG, CC. REP.

LIBER 3 PAGE 81
REMONUMENTATION

RECORDED
HILLSDALE CO. MICH.
97919
'94 DEC 14 AM 11 59

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in

Located In: HILLSDALE (County)
Corner Code #
T 5S R 1W G4, G5
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

SURVEY & REMONUMENTATION

Register of Deeds Stamp & File Number

APR 27 1995

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John E. Maxson, in a field survey on 4 November, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- | | |
|--|--|
| G-4
GLO, 1824, 12"W.Oak, N01W, 97 lks
10"B.Oak, S88W, 46 lks
LCRC, 1972, Burris, L1, P169
Hatt Survey, 1973, L1, P228
Iron Rod
LCRC, 1985, VanGieson, L2, P71
1/2" Iron Rod | G-5
GLO, 1824, 20"W.Oak, S50E, 243 lks
20"W.Oak, S46W, 603 lks
LCRC, 1973, Hatt, L1, P263
3/4" pipe
Vangieson Survey, 1990, L619, P488
1/2" pipe |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|---|
| G-4
Found iron from VanGieson LCRC
and accepted as the best available
evidence of the position of the
original Corner | G-5
Found Iron from VanGieson Survey
and accepted as the best available
evidence of the position of the
original Corner |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| G-4
Reset 5/8 x 36 rebar w/cap
N60E 45.48' 10"ETm
S45E 123.74' 15"Poplar
S45W 142.63' P.Pole
N60W 315.70' P.Pole | G-5
Reset 5/8 x 36 rebar w/cap
N60W 185.40' P.Pole
N10W 133.10' P.Pole
N30E 237.59' P.Pole
S50E 149.59' 15"Oak |
|---|---|



Signed by *John E. Maxson*
Surveyor's Michigan License No. 27454

12 December, 1994