

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 1990 AT A MEETING HELD ON 12-28-94 AT RINGENBERG, CO. REP.

97910

RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 DEC 14 AM 11 58

Judy VanZandt
REG. OF DEEDS

For corners in

HILLSDALE
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5S R 1W
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

11, I3, I5

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John E. Maxson, in a field survey on 4 November 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|--|
| <p>I-1
GLO, 1824, 9"W.Oak, N58W, 24 lks
9"W.Oak, S43E, 16 lks
Standard Corner West 145 lks
Geo. Mark, 1885, No. 998, Stake
LCRC, 1986, Leone, L556, P181
Harrison Monument</p> | <p>I-3
GLO, 1824, 14"B.Oak, S71E, 69 lks
18"W.Oak, S62W, 73 lks
LCRC, 1986, VanGieson, L2, P69
Set pipe</p> | <p>I-5
GLO, 1824, Post, no witness
LCRC, 1975, Ringenberg, L1, P498
set iron w/cap
VanGieson Survey, 1983, L1, P825
capped iron (Ringenberg)</p> |
|--|---|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | |
|--|--|---|
| <p>I-1
Found monument from Leone LCRC and accepted as the best available evidence of the position of the original Corner</p> | <p>I-3
Found iron from VanGieson LCRC and accepted as the best available evidence of the position of the original Corner</p> | <p>I-5
Found iron from Ringenberg LCRC and accepted as the best available evidence of the position of the original Corner</p> |
|--|--|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|---|---|
| <p>I-1
Reset 5/8 x 36 rebar w/cap
N13W 38.25' 40"Oak
N48E 42.12' P.Pole
N65E 67.60' 15"Oak
S62E 38.35' 4"BoxElder
S32E 60.81' P.Pole
West 93.82 Con.Mon,
I-3, T4S-R1W</p> | <p>I-3
Reset 5/8 x 36 rebar w/cap
N15E 56.71' 15"Apple
N50E 77.37' 15"Apple
N85E 55.42' 8"Cherry
N20W 59.86' 15"Apple</p> | <p>I-5
Reset 5/8 x 36 rebar w/cap
N60E 29.79' 12"Oak
S40E 4.92' 8"Ash
S30W 19.69' 10"Oak
N45W 18.07' 10"Oak</p> |
|---|---|---|

Signed by John E. Maxson Date 12 December, 1994
Surveyor's Michigan License No. 27454

