

APPROVED BY THE HILLSDALE COUNTY SURVEYOR PEER GROUP AS THE OFFICIAL SURVEYOR UNDER MICHIGAN PUBLIC ACT 346 1990 AT A MEETING HELD ON 12-14-94
AL RINGENBERG, CO. REPR

LIBER 3 PAGE 72
REMONUMENTATION

97910

RECORDED
HILLSDALE CO. MICH.

'94 DEC 14 AM 11 58

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Julie VanZandt
REG. OF DEEDS

corners in

HILLSDALE
(County)

Public Land Survey T 5S R 1W
T R
T R
T R

Property Controlling S T R
in Section S T R
Miscellaneous S T R
Property in Sec. S T R

Located In: Corner Code #

I 1 13 I 5

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

Lot No. _____, Recorded Plat _____
Private Claims _____

John E. Maxson, in a field survey on 4 November 1994

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

I-1 GLO, 1824, 9"W.Oak, N56W, 24 lks 9"W.Oak, S43E, 16 lks Standard Corner West 145 lks Geo. Mark, 1885, No. 998, Stake LCRC, 1986, Leone, L556, P181 Harrison Monument	I-3 GLO, 1824, 14"W.Oak, S71E, 69 lks 18"W.Oak, S62W, 73 lks LCRC, 1986, VanGieson, L2, P69 Set pipe	I-5 GLO, 1824, Post. no witness LCRC, 1975, Ringenberg, L1, P498 set iron w/cap VanGieson Survey, 1983, L1, P825 capped iron (Ringenberg)
---	--	--

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found monument from Leone LCRC and accepted as the best available evidence of the position of the original Corner	I-3 Found iron from VanGieson LCRC and accepted as the best available evidence of the position of the original Corner	I-5 Found iron from Ringenberg LCRC and accepted as the best available evidence of the position of the original Corner
--	--	---

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Reset 5/8 x 36 rebar w/cap N13W 38.25' 40"Oak N48E 42.12' P.Pole N65E 67.60' 15"Oak S62E 38.35' 4"BoxElder S32E 60.81' P.Pole West 93.82 Con.Mon, I-3, T4S-R1W	I-3 Reset 5/8 x 36 rebar w/cap N15E 56.71' 15"Apple N50E 77.37' 15"Apple N85E 55.42' 8"Cherry N20W 59.86' 15"Apple	I-5 Reset 5/8 x 36 rebar w/cap N60E 29.79' 12"Oak S40E 4.92' 8"Ash S30W 19.69' 10"Oak N45W 18.07' 10"Oak
--	---	---

Signed by *John E. Maxson* Date 12 December, 1994
Surveyor's Michigan License No. 27454

