

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990 AT MEETING HELD ON 11-28-94 AL RINGENBERG, CO. REF.

LIBER 3 PAGE 75 **97913**  
 REMONUMENTATION

RECORDED  
 HILLSDALE CO. MICH.  
 '94 DEC 14 AM 11 59

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

*Judy VanZandt*  
 REG. OF DEEDS

For corners in

HILLSDALE  
 (County)

Located In:

Corner Code ##

- 1. Public Land Survey T 5S R 1W
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

F1 I-4

**SURVEY &  
 REMONUMENTATION**

APR 27 1995

Register of Deeds Stamp & File Number

**COMMISSION**

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John E. Maxson, in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

F-1 GLO did not set this Corner	I-4 GLO, 1824, 12" B. Oak, ROSE, 31 lks 7" W. Oak, S57.5W, 21 lks LCRC, 1979, Keller, L1, P619 3/4" Iron w/cap (Suydam) VanGieson Survey, 1982, L1, P825 3/4" Pipe LCRC, 1986, VanGieson, L2, P69 Set 3/4" Pipe at midpoint
------------------------------------	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F-1 No evidence of this Corner was found. Reset this corner from the Plat of "HIGHLAND HILLS" as the best available position of the original Corner	I-4 Found iron from Keller LCRC and accepted as the best available evidence of the position of the original Corner. Also found 3/4" Pipe from VanGieson LCRC app. 37 feet South of Keller Iron to be used as property controlling Corner
--	---

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-1 Reset 5/8 x 36 rebar w/cap South 2.00' C. Line Vicary Rd. South 33.26' 42" Oak S48W 35.03' 5" Cherry S39E 41.31' P. Pole N22E 34.59' Stop Sign Post	I-4 Reset 5/8 x 36 rebar w/cap S02E 48.75' Fence Post N02E 4.95' Fence Post N10W 119.70' P. Pole West 49.38' 4" Maple South 37.44' 3/4" Pipe, Prop. Cont. Cor. from LCRC, L2, P69
---	--

Signed by *John E. Maxson* Date 12 December, 1994  
 Surveyor's Michigan License No. 27454

