

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL REFER UNDER MICHIGAN PUBLIC ACT 348 1980 AT A MEETING HELD ON 12-28-94
AL RINGENBERG, CO. REP.

LIBER 3 PAGE 80

97918

RECORDED
HILLSDALE CO. MICH.

REMONUMENTATION

'94 DEC 14 AM 11 59

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Julia VanZandt
REG. OF DEEDS

For corners in

HILLSDALE
(County)

Located In:

Corner Code #7

- 1. Public Land Survey T 5S R 11W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

J5 K2
**SURVEY &
REMONUMENTATION**
APR 27 1995
COMMISSION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John E. Maxson, in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|-----|--|-----|---|
| J-5 | GLO, 1824, 12"W. Post, N86E, 15 lks
18"B. Oak, S41W, 45 lks
LCRC, 1980, Keller, L1, P619
Iron w/cap | K-2 | GLO, 1824, 10"B. Oak, N21E, 6 lks
14"B. Oak, S21W, 24 lks
LCRC, 1975, Richard, L1, P487
set pipe |
|-----|--|-----|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | | | |
|-----|---|-----|--|
| J-5 | Found Iron from Keller LCRC
and accepted as the best available
evidence of the position of the
original Corner | K-2 | Found iron from Richard LCRC
and accepted as the best available
evidence of the position of the
original Corner |
|-----|---|-----|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|------|----------------------------|------|----------------------------|
| J-5 | Reset 5/8 x 36 rebar w/cap | K-2 | Reset 5/8 x 36 rebar w/cap |
| S85W | 30.75' Tele. Riser | S70W | 75.60' 24" Maple |
| S30W | 112.50' 20" Box Elder | N30W | 22.74' 14" Locust |
| N48W | 100.89' 48" Willow | N05W | 24.65' Conc. Post |
| N19W | 99.11' 36" Maple | S05E | 18.04' 12" Tr. Locust |



Signed by *John E. Maxson*
Surveyor's Michigan License No. 27454

Date 12 December, 1994