

ACCEPTED BY THE HILLSDALE COUNTY SURVEYOR PEER GROUP AS THE OFFICIAL SURVEY UNDER MICHIGAN PUBLIC ACT 348 1990 AT MEETING HELD ON 28-94  
AL RINGENBERG, CO. REP.

LIBER 3 PAGE 86 97924

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
HILLSDALE CO. MICH.

'94 DEC 14 AM 11 59

Judy VanZandt  
REG. OF DEEDS

For corners in

HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey	T <sup>5S</sup> R <sup>1W</sup>	M1.
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

SURVEY &  
REMONUMENTATION  
APR 27 1995  
COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John E. Maxson, in a field survey on 4 November, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-1  
GLO, 1815, 7" B. Oak, N36E, 7 lks  
2" W. Oak, S26W, 37 lks  
Co. Record, 1910, Blair,  
Stone  
LCRC, 1977, Hooth, L1, P545  
3/4" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1  
Gutekunst found stone below grade  
and accepted as the best available  
evidence of the position of the  
original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1  
4" dia. Conc. Monument w/cap  
N37E 45.60' 10" Walnut  
N60E 56.00' 24" Walnut  
S38E 53.45' Con. ROW Marker  
S82E 92.92' 30" Hickory

Signed by John E. Maxson  
Surveyor's Michigan License No. 27454

Date 12 December, 1994

