

Judy VanZandt
REG. OF DEEDS

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY FEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT MEETING HELD ON
11-28-94
[Signature]
AL RINGENBERG, CO. REP.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE
(County)

Located In:

Corner Code #

1. Public Land Survey

T 5S R 1W

M3, M4

**SURVEY &
REMONUMENTATION**

2. Property Controlling
in Section

S ___ T ___ R ___
S ___ T ___ R ___

APR 27 1995

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___
S ___ T ___ R ___

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John E. Maxson in a field survey on 4 November, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|------------------------------------|------------------------------------|
| M-3 | M-4 |
| GLO, 1824, 12"B.Oak, N02W, 385 lks | GLO, 1824, 7"Hickory, S14E, 52 lks |
| 14"B.Oak, N01E, 388 lks | 16"B.Oak, N57W, 37 lks |
| LCRC, 1977, Hooth, L1, P546 | LCRC, 1980, Suydam, L2, P5 |
| Iron w/cap #12030 | Plat Monument |
| | LCRC, 1983, Ringenberg, L2, P45 |
| | Plat Monument |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|------------------------------------|-------------------------------------|
| M-3 | M-4 |
| Found iron from Hooth LCRC | Found monument from Ringenberg LCRC |
| and accepted as the best available | and accepted as the best available |
| evidence of the position of the | evidence of the position of the |
| original Corner | original Corner |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|-----------------------------------|----------------------------|
| M-3 | M-4 |
| Reset 5/8 x 36 rebar w/cap | Reset 5/8 x 36 rebar w/cap |
| N65E 121.66' 4"Elm | North 53.89' 3"Cherry |
| N45W 50.00' 1/2"Iron w/cap #27454 | East 2.22' 4"Cherry |
| S45W 50.00' 1/2"Iron w/cap #27454 | South 3.25' 3"Cherry |
| S45E 50.00' 1/2"Iron w/cap #27454 | S80W 25.00' 3"Cedar |
| North 131.23' 3/4"Iron pipe | North 187.20' 24"Oak |
| A-3, T5S-R1E | |



12 December, 1994

Signed by *John E. Maxson* Date _____
Surveyor's Michigan License No. 27454