

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Hillsdale
 (County)

Located In: Corner Code //

1. Public Land Survey	T	55	R	1W	18
	T	55	R	1W	H8
	T	55	R	1W	110
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

110 October 04, 1991
 H8 September 19, 1991

I, Gary C. Bilow, in a field survey on 18 September 19, 1991, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

18: Post established by U.S. Deputy Surveyor R. Clark in 1824 - accessories: B. Ash 8", N66E 18 links and B. Ash 6", S40W 12 links.
 H8: Corner not established by U.S. Government Survey. Found no evidence of corner being established.
 110: Post established by U.S. Deputy Surveyor R. Clark in 1824 - accessories: Hickory 5", N33W 16-1/2 links and W. Ash 12", S61E 9 links. Corner notes obtained from A. Ringenberg, PE/LLS #15103, show he reestablished of corner by accepting N-S fence line and prorating distance from corner 111. Ringenberg set a 3/4" bar 10' +/- north of Mercer Road - accessories: N20W 12.82", PK in 6" Maple; S30E 43.07', PK in 6" Walnut; S40W 47.08', PK in double 6" Walnut in 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

18: Reestablished corner at the intersection of N-S and E-W fence lines.
 H8: Established corner at the intersection of the N-S and E-W 1/4 lines.
 110: Found 5/8" bar and recovered one (1) of Ringenberg's accessories. Accepted bar as the best evidence of the original GLO corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

18: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet	H8: Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet	110: Found 5/8" bar 12' north of Mercer Road and 8' east of centerline drive to the south
S3W 59.88', nail & tag in 12" Hickory	S64W 23.40', nail & tag in 16" Walnut	S49W 47.36', nail & tag in twin 13" Walnut
S37E 29.13', nail & tag in 8" Hickory	S26W 49.69', nail & tag in 16" Walnut	S27W 67.08', nail & tag in power pole
N81E 69.09', nail & tag in twin 15" Oak	S9E 27.43', nail & tag in 8" Oak	S25E 42.68', nail & tag in 12" Walnut
N50E 55.78', nail & tag in 14" Oak	S52E 24.47', nail & tag in 12" Walnut	N28W 12.46', nail & tag in 12" Hickory

Signed by Gary C. Bilow Date 3/31/92
 Surveyor's Michigan License No. 26453

