



HILLSDALE COUNTY REMONUMENTATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
HILLSDALE CO. MICH.  
97 SEP 22 PM 12 19

For corners in

<u>HILLSDALE</u>	Located In:	Corner
Code #		
(County)		
MOSCOW TWP.		
1. Public Land Survey	T <u>5</u> S R <u>2</u> W	<u>B-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

*Judy VanZandt*  
REG. OF DEEDS  
SURVEY &  
REMONUMENTATION

OCT 17 1997

COMMISSION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JULY 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9	●												
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
QUARTER CORNER COMMON TO SECTIONS 19-30, MOSCOW TWP

NO INFORMATION AVIABLE SINCE GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE WITH BRICK AROUND, ALSO SMALL IRON OVER STONE, IN LINE WITH FENCE RUNNING SOUTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET 3/4" X 20" REBAR IRON OVER STONE, REMON CAP ON IRON, CI-MONUMENT BOX DURING ROAD REPAVING PROJECT

SQUARE WOOD ANCHOR POST, SOUTH 26.30 TO FACE  
NE CORNER TEL. PED, S47W 32.90'  
EAST END OF DRIVE CULVERT, S78W 222.8'  
CENTER OF 14" OAK, SOUTH 116.4'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*

EDWARD W. REED

Date JULY 26, 1997

Surveyor's Michigan License No. 33985

