

126330

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON [Signature] AL RINGENBERG, CO. REC.

LIBER 3 PAGE 190

RECORDED HILLSDALE CO. MICH.

HILLSDALE COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'97 SEP 22 PM 12 19

For corners in

HILLSDALE Located In: Corner Code # (County) MOSCOW TWP. 1. Public Land Survey T 5 S R 2 W C-9 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

Judy VanZandt REG. OF DEEDS SURVEY & REMONUMENTATIO OCT 17 1997 COMMISSION Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, EDWARD W. REED, in a field survey on JULY 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Cell (9, C) contains a black dot.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER COMMON TO SECTIONS 19-20-29-30, MOSCOW TWP. NO INFORMATION AVAILABLE SINCE GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE WITH BRICK IN INTERSECTIONS OF ROADS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX DURING ROAD REPAVING PROJECT NAIL & SHINER SOUTH SIDE OF 30" MAPLE, N 45 E 53.40' FACE OF TEL. PED., S 50 E 118.0' CORNER POST OF YARD FENCE, S 30 E 39.28' NORTH END OF ROAD CMP, N 70 W 87.0' SOUTH END ROAD CMP, S 70 W 88.0'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by [Signature] EDWARD W. REED

Date JULY 26, 1997

Surveyor's Michigan License No. 33985

