

126326



LIBER 3 PAGE 186

RECORDED

HILLSDALE COUNTY REMONUMENTATION CORNER HILLSDALE CO. MICH.  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'97 SEP 22 PM 12 19

For corners in

HILLSDALE Located In: \_\_\_\_\_ Corner \_\_\_\_\_  
 Code # \_\_\_\_\_  
 (County)  
 MOSCOW TWP.  
 1. Public Land Survey T 5 S R 2 W D-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

*Judy Varnjandt*  
 REG. OF DEEDS  
 SURVEY &  
 REMONUMENTATION  
 OCT 17 1997  
 COMMISSION  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JULY 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 QUARTER CORNER COMMON TO SECTIONS 20 & 29, MOSCOW TWP

1984: J. WILCOX, SURVEYOR - SET IRON AND CAP FROM COUNTY SURVEYORS WITNESS AS RECORDED BY GEORGE MARK IN BOOK NO, 7, PAGES 172-173 ON APRIL 11, 1883, RECORDED IN LCRC # 8807, LIBER 2, PAGE 65

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON WITH CAP AS DESCRIBED BY WILCOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 SET 3/4" X 30" IRON ROD WITH REMON CAP IN CI-MONUMENT BOX DURING ROAD REPAVING PROJECT

- FACE OF POWER POLE, S19W 51.98'
- FACE OF FENCE POST, N56E 33.30'
- SW CORNER HOUSE, N45W 84.8'
- CENTER OF 14" PINE, N58W 120.0'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed* Date JULY 25, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985

