



126323

HILLSDALE COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED HILLSDALE CO. MICH.

'97 SEP 22 PM 12 17

For corners in

Form with fields: HILLSDALE (County), Located In: Corner, Code #, MOSCOW, 1. Public Land Survey T 5 S R 2 W H-9, 2. Property Controlling in Section S T R, 3. Miscellaneous Property in Sec. S T R

Judith VanZandt REG. OF DEEDS SURVEY & REMONUMENTATION OCT 17 1997 COMMISSION Register on Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, EDWARD W. REED, in a field survey on JULY 18, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at row 9, column H.

A. Description of original monument and accessories and/or subsequent restoration: QUARTER CORNER COMMON TO SECTIONS 22-27

NO INFORMATION AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" SOLID IRON BAR 30" DEEP IN ORIGINAL SOIL, IN LINE WITH FENCE RUNNING NORTH. ON APPROXIMATE EAST-WEST SECTION LINE, 2' WEST OF MIDWAY POINT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET 3/4"X 30" REBAR IRON AND REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD SURFACE.

IN LINE WITH FENCE RUNNING NORTH
NAIL & WASHER E. SIDE 36" OAK, N45W 47.08'
SQUARE WOOD ANCHOR POST, S45W 52.41'
NW CORNER OF PORCH, HOUSE # 6531, S40E 123.00'
NAIL & WASHER W. SIDE 30" MAPLE, S20E 83.15'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by [Signature] EDWARD W. REED

Date JULY 18, 1997

Surveyor's Michigan License No. 33985

