

024402

RECORDED
HILLSDALE CO. MICH.

99 NOV -1 AM 9:01

ACCEPTED BY THE HILLSDALE COUNTY SURVEY BOARD AS THE CORNER UNDER MICHIGAN PUBLIC ACT NO. 1825 AS A MEETING HELD AT HILLSDALE, MICH. AL BINGENBERG, COUNTY CLERK

HILLSDALE COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

John J. VanFleet
REG. OF DEEDS

For corners in

HILLSDALE COUNTY Located In: Corner Code #
SCIPIO TWP

- 1. Public Land Survey T 5 S R 3 W G-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____
T _____ R _____
- 3. Miscellaneous S _____
T _____ R _____
Property in Sec. S _____
T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCT. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

NORTHWEST CORNER, SECTION 3
NORTHEAST CORNER, SECTION 4

A. Description of original monument and accessories and/or subsequent restoration:

1825: GLO CORNER SET
NO OTHER INFORMATION AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG AND FOUND 10" POINTED GRANITE STONE, FITTING APPROXIMATE GLO OFFSET DISTANCE AND FENCE LINES EAST, WEST & SOUTH

SET 3/4" X 30" REBAR (OVER STONE) & CAP IN CAST IRON MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 30" REBAR WITH CAP IN CAST IRON MONUMENT BOX

- FACE OF TELEPHONE PEDESTAL N 65 E 68.95'
- SPIKE IN SOUTH SIDE OF POWER POLE S 70 E 128.00'
- SPIKE IN SOUTH SIDE OF POWER POLE S 54 W 32.70'
- SPIKE IN SOUTH SIDE OF POWER POLE N 6 W 99.15'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W. REED

Date OCT 18, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

