

ACCEPTED BY THE HILLSDALE COUNTY SURVEY BOARD GROUP AS THE CORNER UNDER MICHIGAN PUBLIC ACT 1970-1028-20 MEETING OCT 18 1999 AL HINGENBERG, CO. 1 1 1 1

HILLSDALE COUNTY REMONUMATION PROGRAM LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE COUNTY Located In: Corner Code # SCIPIO TWP

- 1. Public Land Survey T 5 S R 3 W G-2
2. Property Controlling in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

024403 RECORDED HILLSDALE CO. MICH. 09 OCT 1999 - 1 AM 9:01 Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, EDWARD W. REED, in a field survey on OCT 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A black dot is located at the intersection of row 2 and column G.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 3 & 4

A. Description of original monument and accessories and/or subsequent restoration:

1825: GLO CORNERS SET, NO OTHER INFORMATION AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


UNABLE TO LOCATE ANY EVIDENCE OF OLD CORNER SET CORNER AT GLO DISTANCES AND ON SECTION LINE NORTH & SOUTH

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 30" REBAR WITH CAP

- WOOD ANCHOR POST EAST 37.0'
18" OAK WEST 36.2'
8" TWIN CHERRY S 62 W 37.4'
30" OAK S 29 E 56.6'
STEEL GAS LINE MARKER S 27 W 86.5'
0.6 NORTH OF E-W FENCE LINE

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



Signed by Edward W. Reed EDWARD W. REED

Date OCTOBER 18, 1999

Surveyor's Michigan License No. 33985