



**HILLSDALE COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 3 PAGE 308

For corners in

<u>HILLSDALE COUNTY</u>	Located In:	Corner Code #
SCIPPIO TWP.		
1. Public Land Survey	T <u>5</u> S R <u>3</u> W	<u>G-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

**021812**  
RECORDED  
HILLSDALE CO. MICH.  
99 AUG 23 PM 4:00  
*July VanJanet*  
REG. OF DEEDS  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JUNE 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

CORNER COMMON TO SECTIONS 3, 4, 9 & 10

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GLO CORNER SET
- 1872: GEO. A. MARK, SURVEYOR, STONE
- 1973: ROBERT E. BURRIS, SR., FOUND T IRON, LCRC RECORDED IN LIBER 1, PAGE 355

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND T IRON FITTING WITNESSES OF BURRIS' LCRC  
SET 3/4" IRON WITH REMON CAP IN CAST IRON MONUMENT BOX FLUSH WITH PAVED ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" IRON WITH REMON CAP IN CAST IRON BOX
- N 62 W 77.33' - TOP/CENTER OF TELEPHONE PEDESTAL
- S 61 W 46.37' - TOP/CENTER OF TELEPHONE PEDESTAL
- N 28 E 65.14' - PK NAIL SE SIDE OF POWER POLE
- S 41 E 50.03' - NW BOLT AT BASE OF MARATHON SIGN
- S 52 E 38.65' - TOP/CENTER OF STORM DRAIN

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*  
EDWARD W, REED

Date JUNE 18, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

