

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON _____ AT _____ AL RINGENBERG, CO. REP.

**HILLSDALE COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 309

021813

RECORDED
HILLSDALE CO. MICH.
99 AUG 23 PM 4:00

Judy Vanjones
REG. OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>HILLSDALE COUNTY</u>	Located In:	Corner Code #
SCIPIO TWP.		
1. Public Land Survey	<u>T 5 S R 3 W</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 9 & 10

A. Description of original monument and accessories and/or subsequent restoration:

1825: GLO CORNER SET
1872: GEO. A. MARK, SURVEYOR, STONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RR SPIKE FLUSH WITH ROAD, NO EVIDENCE OF STONE
SET 3/4" IRON (IN PLACE OF RR SPIKE) WITH REMON CAP IN CAST IRON MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" IRON WITH REMON CAP IN CAST IRON BOX
S 18 W 98.74' - NAIL AND CAP EAST SIDE 40" OAK
S 17 E 78.25' - NAIL AND CAP WEST SIDE 40" OAK
S 46 E 39.28' - FACE OF POWER POLE
S 90 W 37.15' - NAIL AND CAP SOUTH SIDE 12" CHERRY

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W. REED



Date JUNE 18, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													