

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990 MEETING HELD ON 8-1-99 AT RINGENBERG, CO. REG.

**HILLSDALE COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 310

**021814**

RECORDED  
HILLSDALE CO. MICH.

99 AUG 23 PM 4:00

*Judy VanJames*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

For corners in

HILLSDALE COUNTY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
SCIPIO TWP.

1. Public Land Survey T 5 S R 3 W G-5  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

Property in Sec. S \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JUNE 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**CORNER COMMON TO SECTIONS 9, 10, 15 & 16**

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GLO CORNER SET
- 1872: GEO. A. MARK, SURVEYOR, SURVEY #659, STONE
- 1872: GEO. A. MARK, SURVEYOR, SURVEY #660, STONE & BRICK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RR SPIKE, NO EVIDENCE OF STONE OR BRICK  
 SET 3/4" IRON (IN PLACE OF RR SPIKE) WITH REMON CAP IN CAST IRON MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" IRON WITH REMON CAP IN CAST IRON BOX
- S 17 E 99.15' - TOP/CENTER OF TELEPHONE PEDESTAL
- S 56 W 48.90' - TOP/CENTER OF CONCRETE POST
- S 70 E 60.72' - SOUTH END OF 18" CULVERT (TOP/CENTER)
- S 39 E 61.0' - TOP/CENTER OF BELL SYSTEM MANHOLE COVER
- C/L N-S ROAD
- C/L E-W ROAD

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*  
 EDWARD W. REED

Date JUNE 18, 1999

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

