



**HILLSDALE COUNTY REMONUMATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 312

**021816**

RECORDED  
HILLSDALE CO. MICH.

99 AUG 23 PH 4:00

*Justy VanJames*  
REG. OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>HILLSDALE COUNTY</u>	Located In:	Corner Code #
SCIPID TWP.		
1. Public Land Survey	<u>T 5 S R 3 W</u>	<u>G-7</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous	S <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
Property in Sec.	S <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JUNE 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3												
4	7	8			9		10		11		12	
5												
6	18	17			16		15		14		13	
7												
8	19	20			21		22		23		24	
9												
10	30	29			28		27		26		25	
11												
12	31	32			33		34		35		36	
13												

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 15, 16, 21, & 22

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: GLO CORNER SET
- 1872: GEO. A MARK, SURVEYOR, SURVEY #660, STONE & BRICK
- 1979: BRUCE LEONE, SURVEYOR, SURVEY TIED TO CORNER
- 1979: TIMOTHY B. VAN GIESON, SURVEYOR, FOUND 16" X 8" POINTED GRANITE STONE WITH BROKEN CLAY TILE OR CROCKERY, SET COUNTY ISSUE MONUMENT, LCRC RECORDED IN LIBER 1, PAGE 613,

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- FOUND HARRISON MARKER FITTING WITNESSES OF VAN GIESON-NO EVIDENCE OF STONE
- REMOVED HARRISON MARKER
- SET 3/4" IRON (IN PLACE OF HARRISON MARKER) WITH REMON CAP IN CAST IRON MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" IRON WITH REMON CAP IN CAST IRON BOX
- S 65 E 96.42' - FACE OF TELEPHONE PEDESTAL
- N 70 E 44.83' - FACE OF 6" ROUND WOOD CORNER POST
- N 15 E 186.68' - CENTER OF 30" OAK
- S 10 W 189.09' - CENTER OF 30" OAK
- S 30 W 46.28' - CENTER OF 30" HICKORY
- N 70 W 94.05' - 36" OAK (NOW STUMP)
- 3.0' WEST OF C/L N-S ROAD
- 9.6' N OF C/L E-W ROAD
- AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *Edward W. Reed*

Date JUNE 18, 1999

EDWARD W. REED

Surveyor's Michigan License No. 33985