

APPROVED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL SURVEY UNDER MICHIGAN PUBLIC ACT 345 ON 8/23/99 AT A MEETING HELD ON AL RINGENBERG, CO. REP.

**HILLSDALE COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 316

021820

RECORDED
HILLSDALE CO. MICH.
30 AUG 23 PM 4:01

Judy VanZandt
REG. OF DEEDS

Register of Deeds Stamp & File Number

For corners in

HILLSDALE COUNTY Located In: _____ Corner Code # _____
 SCIPIO TWP & FAYETTE TWP.

1. Public Land Survey T 5 S R 3 W G-11
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____
 T _____ R _____

3. Miscellaneous S _____
 T _____ R _____

Property in Sec. S _____
 T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTION 27, 28, 33 & 34

A. Description of original monument and accessories and/or subsequent restoration:

1825: GLO CORNET SET
 1884: GEO. A . MARK, SURVEYOR, STONE; W OAK 8, N 86 1/4 E 45 LINKS
 1971: A.J. HATT, SURVEYOR, SET RR SPIKE AT PROPORTIONAL DISTANCE N & S AND 45 LINKS FROM W OAK AS MENTIONED BY MARK, LCRC RECORDED IN LIBER 1, PAGE 31

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RR SPIKE FITTING WITNESSES OF A.J. HATT
 SET 3/4" X 30" IRON (IN PLACE OF RR SPIKE) WITH REMON CAP IN CAST IRON MONUMENT BOX

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 30" IRON WITH REMON CAP IN CAST IRON MONUMENT BOX
 N 85 E 29.95' - NAIL AND CAP NORTH SIDE OF 34" OAK
 N 40 E 36.8' - NAIL AND CAP WEST SIDE OF 34" WALNUT
 S 32 W 61.23' - NAIL AND CAP EAST SIDE TRIPLE POPLAR
 N 32 W 59.55' - NAIL AND CAP EAST SIDE OF 24" BUTTERNUT


AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*

EDWARD W. REED

Surveyor's Michigan License No. 33985

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |



Date JUNE 18, 1999