



**HILLSDALE COUNTY REMONUMATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

LIBER 3 PAGE 317

021821

RECORDED
HILLSDALE CO. MICH.

99 AUG 23 PM 4:01

Julie Van James
REG. OF DEEDS

Register of Deeds Stamp & File Number

For corners in

<u>HILLSDALE COUNTY</u>	Located In:	Corner Code #
FAYETTE TWP.		
1. Public Land Survey	<u>T 5 S R 3 W</u>	<u>G-13</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___	_____
	T ___ R ___	_____
3. Miscellaneous	S ___	_____
	T ___ R ___	_____
Property in Sec.	S ___	_____
	T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JUNE 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

SOUTHEAST CORNER SECTION 33
SOUTHWEST CORNER SECTION 34

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1825: GLO CORNER
GLO OFFSET TO NORTHEAST CORNER SECTION 4 = 29 LINKS
1988: RUSSELL L. ROON, SURVEYOR, FOUND 1/2" IRON ROD WITH RLS CAP FITTING PREVIOUS SOURCE, LCRC RECORDED IN LIBER 597, PAGE 671

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" X 18" REBAR AND CAP (UNABLE TO READ CAP) FITTING WITNESS OF LCRC IN LIBER 597, PAGE 671
REMOVED 1/2" IRON
SET 3/4" X 30" IRON
SET REMON CAP ON IRON IN CAST IRON MONUMENT BOX 5" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4" X 30" IRON WITH REMON CAP IN CAST IRON BOX
WEST 19.10' (29 LINKS) - NE CORNER SECTION 4
N 25 W 78.35' - SE CORNER MONUMENT OF M. B. POWELL 1822 TO 1906
N 30 W 34.41' - PK NAIL E. SIDE 30" MAPLE
S 50 E 32.38' - PK NAIL SIDE P.P.
S 60 W 88.83' - NE CORNER MONUMENT BASE OF J. D. DENNIS 1804 TO 1883
N 64 W 53.64' - SW CORNER BARN

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *Edward W. Reed*
EDWARD W. REED

Date JUNE 2, 1999

Surveyor's Michigan License No. 33985

