

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1880 AT A MEETING HELD ON _____
Al Ringenberg, Co. Rep.
 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 142

118410

RECORDED
 HILLSDALE CO. MICH.

HILLSDALE COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

'96 DEC 20 AM 9 09

For corners in

<u>Hillsdale</u> (County)	Located In:	Corner Code #
<u>Scipio Twp.</u>		
1. Public Land Survey	T <u>5S</u> R <u>3W</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Judy VanZandt
 REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher, in a field survey on November 6, 1996.

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:
 Original Government Survey by Clark, 1823: 12" B. Oak S. 13° W. 50 lks.; 18" B. Oak N. 57° W. 65 lks. GLO proration places this corner 119 lks. (78.54') South of N.W. corner Sec. 18, Town 5 South, Range 2 West.
 Survey #1063 5-21-1888 by George Mark: Stone, brick & iron.
 LCRC Liber 1, Page 245, #6315 Dec. 28, 1972 by A. John Hatt, R.L.S. #9208: Fd. long pointed stone surrounded by stones & brick 24" under pavement. Set cast iron monument (Harrison Marker) over top of stone. Nail S.E. side 14" Walnut, S. 60° W. 93.63'; Nail E. side 46" Maple N. 15° W. 121.65'; Nail N.W. side 36" Maple N. 40° E. 119.36'; Nail N. side tel. pole S. 55° E. 30.57'.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 On 11-6-96 found Harrison Marker over stone & brick from LCRC references.
 Three LCRC witnesses remain.

SURVEY &
 REMONUMENTATION

MAY 16 1997

COMMISSION



3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Replaced Harrison Marker with Hillsdale County remonumentation bar with cap in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

1.5' W. of centerline Milnes Road.
 Top center tel. stanchion S. 50° E. 30.52'.
 N.E. cor. building S. 72° W. 108.5'.
 S.W. cor. house N. 38° E. 146.0'.
 Cen. 30" Walnut S. 60° W. 93.8'.

Signed by Frederick J. Cutcher Date December 19, 1996
 Surveyor's Michigan License No. 24592