

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1980 AT A MEETING HELD ON _____ AL RINGENBERG, CO. REP.

LIBER 3 PAGE 144 **118412**
 HILLSDALE COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 HILLSDALE CO. MICH.
 '96 DEC 20 AM 9 09

Judith Varnjarndt
 REG. OF DEEDS

For corners in

Hillsdale Located In: Corner Code #
 (County)
Scipio Twp.

1. Public Land Survey T 5S R 3W M-9
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher, in a field survey on December 16, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original Government Survey by Clark, 1823: 30" B. Oak S. 29° W. 19 lks.; 14" Hickory N. 34° W. 37 lks. GLO proration places this corner 136 lks. (89.76') South of N.W. cor. Sec. 30, Town 5 South, Range 2 West.
 Survey #729 3-6-1876 by George Mark: Stone.
 Records of Ringenberg, 11/30/59 H.J.S. & T.H.A.: Set 1/2" iron rod 18" long in blacktop road by witnesses; N.E. cor. conc. blk. serv. station S.W. 65.50'; 36" Elm S.W. 64.73'; Pwr. Pole W.N.W. 51.55'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 1/2" iron rod from above reference.
 Only N.E. cor. of block building remains.

SURVEY & REMONUMENTATION

MAY 16 1997



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Hillsdale County remonumentation bar with cap in monument box and is accepted as the best available evidence of the position of the original corner.

6' West of centerline of Milnes Rd.
 Centerline of US-12 N. 30° W. 63.0' (as marked).
 N. & S. S. side corner post N. 42° E. 57.3'.
 N.E. cor. conc. blk. bldg. (former serv. sta.) S. 50° W. 64.30'.
 S.E. cor. conc. blk. bldg. (former serv. sta.) S. 21° W. 76.39'.
 Top center tel. stanchion S. 17° E. 86.23'

Signed by Frederick J. Cutcher Date December 19, 1996
 Frederick J. Cutcher
 Surveyor's Michigan License No. 24592