

ACCEPTED BY THE HILLSDALE SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT OF 1970 AT A MEETING HELD ON \_\_\_\_\_ AL RINGENBERG CO. REC.

022234  
RECORDED  
HILLSDALE CO. MICH.  
99 SEP -2 AM 9:15  
*July Vanjander*  
REG. OF DEEDS

LIBER 3 PAGE 319  
HILLSDALE COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE \_\_\_\_\_ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)  
LITCHFIELD TWP.

1. Public Land Survey T5S R4 W A-13  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Frederick J. Cutcher, in a field survey on July 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			1
3													
4	7			8			9			10			12
5													
6	18			17			16			15			13
7													
8	19			20			21			22			24
9													
10	30			29			28			27			25
11													
12	31			32			33			34			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O., 2/3/1825, John Mullett: W. Ash 9° N 52° E. 30 lks; Ironwood 7° S. 81° W. 89 lks.

Survey No. 755, 11/8/1876, Geo. A. Mark: Stone (no references)

Survey L. 1, P. 121, 5/19/1972, A.J. Hatt: Iron pipe in pavement.

LCRC 2678, L. 1., P. 107, 6/6/1972, A.J. Hatt: Set 3/4" iron in pavement to fit occupation S. & E.; Conc. Fed. Aid Marker 1' above ground N.E. 55.24'; Conc. Fed. Aid Marker ground surface S.E. 44.22'; Conc. Fed. Aid Marker 2' above ground, N.W.W. 97.85' (measured to nearest corner of triangle shape).

LCRC No. 209, 1/12/78, Fred Cutcher: 5/8" iron N. of centerline, in line with centerline road North; Triangle conc. marker S. 45° E 44.42' (top cen.); Triangle conc. marker N. 35° E. 55.55' (top cen.); Util. Pole N. 20° W. 77.95' (face). (recorded in Branch Co.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 18" iron rod in centerline intersection of roads.

No references remained from GLO or later surveys or LCRCs.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" diameter iron with County Remonumentation Cap in monument box and is accepted as the best available evidence of the position of the original corner. (Replaced 5/8"x18" iron rod).

Top Cen. Tel. Stan. N. 30° E. 76.85'; top cen. triangular conc. post N. 72° W. 97.87'; p.k. & spotter util. pole N. 20° W. 78.18'; cor. conc. curb N. 83° E. 76.82'; cor. conc. curb S. 11° E. 79.45'



Signed by Frederick J. Cutcher  
Surveyor's Michigan License No. 24592

Date 7/30/99