

RECORDED

HILLSDALE CO. MICH.

'94 NOV 28 AM 11 08

Judy VanZandt
REG. OF DEEDS

LIBER 3 PAGE 46 97387

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE HILLSDALE SURVEY PEER GROUP AS THE ONLY CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 11-10-94
AK MINNENBERG, CO. REF.

For corners in
Hillsdale
(County)

Located In: Corner Code #

- 1. Public Land Survey T 5S R 4W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

C-5

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5			●										
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. Cutcher, in a field survey on July 25, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Survey #1161, June 23, 1893, Geo. Mark, Co. Surveyor: Stone & iron; B. Oak 22" S. 55° E., 60 links.
- Survey #1192, September 6, 1895, Geo. Mark, Co. Surveyor: Stones & plow pt; B. Oak 20" S. 55° E., 60 links.
- Stone & plow point found by Bruce Leone, R.L.S., May, 1979.
- F. J. Cutcher, LCRC, Liber 631, Page 909, May 8, 1991: Found 1/2" iron 5' West of centerline of road and 1' South of centerline of road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x4" long iron rod over 1/2"x10" long iron rod over plow point, brick & stone. Plow point, brick & stone are 1.3' below road surface. Set 3/4"x36" Co. remonumentation bar in monument box. Left stone & plow point undisturbed and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4"x36" County remonumentation bar in monument box
- N.E. Corner concrete post S. 45° W., 30.7' Telephone Stanchion N. 75° W., 74.0'
- Center of power pole S. 20° W., 188.6' Center of power pole N. 50° W., 192.6'
- Face of 12" Maple S. 80° E., 121.0' N.W. corner top of concrete post South 30.05'



Signed by Frederick J. Cutcher

Date November 15, 1994

Surveyor's Michigan License No. 24592