

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON 11-10-94 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 48

97389

RECORDED HILLSDALE CO. MICH.

'94 NOV 28 AM 11 08

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Judy VanZandt*  
REG. OF DEEDS

For corners in  
Hillsdale  
(County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 5S R 4W \_\_\_\_\_ E-3 \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SURVEY &  
REMONUMENTATION

APR 27 1995  
Register of Deeds Stamp & File Number

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3					●								
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. Cutcher, in a field survey on July 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A. E. Ringenberg, LCRC Liber 2, Page 29, June 17, 1981, found iron bar from witnesses of A.J. Hatt.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4"x19" solid iron rod 1.1' below gravel road surface, 8' N. of centerline of gravel road (rod has plastic stake beside it). Replaced iron with 3/4"x36" County remonumentation bar. Top is 0.7' below gravel road surface and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar  
8' North of centerline of gravel road; in line with tree row to South  
P.K. in W. side power pole N. 8° E., 33.71'  
S.W. corner house N. 48° E., 75.10'  
S.E. corner bam N. 37° W., 118.95'  
P.K. NW'LY root 30" Maple S. 44° W., 43.41'



Signed by Frederick J. Cutcher Date November 15, 1994  
Surveyor's Michigan License No. 24592