

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-94 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 57
REMONUMENTATION

97398

RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 08

Judy VanZandt
REG. OF DEEDS

For corners in
Hillsdale
(County)

Located In: Corner Code #/

- 1. Public Land Survey T 5S R 4W
- 2. Property Controlling S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

E-7
**SURVEY &
REMONUMENTATION**
APR 27 1995
COMMISSION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. Cutcher, in a field survey on October 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
Survey #1097, June 11, 1889, R. J. Coryell, Co. Surveyor: Stone; R. Oak 24" S. 69 1/2° E., 100 links; Hickory 7" N. 63 1/4° E., 74 links; Y. Oak 15" N. 48° W., 92 links.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1 1/2"x15" iron pipe on East side of pointed blue stone with deposit of brick. Left stone in place and replaced iron pipe with 3/4"x36" County remonumentation bar; and is accepted as a careful and faithful perpetuation of the position of the original corner.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4"x36" County remonumentation bar;
In centerline of E/W road & in line with road to the South & in line with tree row North
Top center of stone (high point) in yard North 29.87'
Nail & Spotter N.W. side 36" Oak S. 55° W., 47.28'
S.E. corner house siding N. 40° W., 108.10'
Nail & Spotter in S. side Maple 24" N. 75° E., 103.73'



Signed by Frederick J. Cutcher Date October 20, 1994
24592

Surveyor's Michigan License No. _____