

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 342 OF 1990 AT MEETING HELD ON 11-10-94 AL RINGENBERG, CO. REC.

LIBER 3 PAGE 51 97392

RECORDED HILLSDALE CO. MICH.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 08

Judy VanZandt
REG. OF DEEDS

For corners in

Hillsdale

(County)

Located In:

Corner Code ##

- | | | | | |
|------------------------------------|---|----|---|----|
| 1. Public Land Survey | T | 5S | R | 4W |
| | T | | R | |
| | T | | R | |
| | T | | R | |
| 2. Property Controlling in Section | S | | T | R |
| | S | | T | R |
| 3. Miscellaneous Property in Sec. | S | | T | R |
| | S | | T | R |

F-3

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Frederick J. Cutcher, in a field survey on July 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A. J. Hatt, LCRC Liber 1, Page 51, Oct. 20, 1971: found boat spike over stone 6" under road surface from M-99 Hwy. plans

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike 6" below gravel surface over stone. Found gray pieces of clay tile around stone. Set 3/4"x36" Co. remonumentation bar angled over stone. Top of iron bar is where top of boat spike was & is 6" below gravel surface and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar
In centerline of E/W road; in line with tree row N. & S.
Iron w/cap #16042 South 33.0'
S.W. corner concrete block garage N. 30° E., 67.17'
Center of gas pipe line marker S. 65° E., 80.20'
Center 6" cedar (in yard) N. 43° W., 72.5'
S.E. corner concrete block garage N. 48° E., 82.35'



Signed by Frederick J. Cutcher

Date November 15, 1994

Surveyor's Michigan License No. 24592