

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990 AT A MEETING HELD ON 11-10-94 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 52 97393
 REMONUMENTATION

RECORDED
 HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 08

Judy VanZandt
 REG. OF DEEDS

For corners in

Hillsdale
 (County)

Located In:

Corner Code #

- 1. Public Land Survey T 5S R 4W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

F-5

SURVEY &
 REMONUMENTATION

APR 27 1995

COMMISSIONER

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Frederick J. Cutcher, in a field survey on October 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Kurzy Engineers, Dec. 1970: Found 3/8" iron pipe.

M. Dyer, LCRC Liber 1, Page 539, Mar. 28, 1977: Found 1/2" bar 2.5' N of centerline Litchfield Road on fence line.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 7/16"x15" iron bar about 4" below road surface. Dug down about 2' into natural ground, nothing else found.

Replaced iron bar with 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar in monument box

2.5' North of centerline in line with fence to South

Nail & spotter E. side 48" Oak N. 27.18'

Hole in top of concrete anchor post S. 30.00'

Bottom S.W. corner concrete post N. 80° E., 134.50'

Center of pipe line marker #14 N. 65° W., 61.97'



Signed by *Frederick J. Cutcher*

Date November 15, 1994

Surveyor's Michigan License No. 24592