

97394

RECORDED
HILLSDALE CO. MICH.

'94 NOV 28 AM 11 08

Judy VanZandt
REG. OF DEEDS

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
7-10-94
AL RINGENBERG, CO. REC.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Hillsdale

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 5S R 4W
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

G-3

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. Cutcher, in a field survey on July 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

R. E. Burris, LCRC Liber 1, Page 231, Oct. 20, 1972: Found iron rod 6" below road surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found old pump handle & many pieces of gray clay tile. Top of pump handle about 6" below road surface. Replaced pump handle with 3/4"x36" County remonumentation bar and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4"x36" County remonumentation bar
- 4' N. of centerline E/W road, in line with tree row North & South
- Nail & Spotter in wood fence post N. 6° W., 35.28'
- Nail in S.W. side 12" W. Cherry N. 65° W., 66.75'
- Center of 10" spruce (in yard) N. 18° E., 77.75'
- Nail in W. side 12" Maple S. 40° E., 37.85'



Signed by Frederick J. Cutcher

Date November 15, 1994

Surveyor's Michigan License No. 24592