

APPROVED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 1990 AT MEETING HELD ON 10-94 AL RINGENBERG, CO. REC.

RECORDED HILLSDALE CO. MICH. '94 NOV 28 AM 11 08

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in Hillsdale (County)

Located In: Corner Code #

- 1. Public Land Survey T 5S R 4W
- 2. Property Controlling in Section S ___ T ___ R ___
- 3. Miscellaneous Property in Sec. S ___ T ___ R ___

G-6

SURVEY & REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher

I, Frederick J. Cutcher, in a field survey on November 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey #1162, July 14, 1893, George Mark, County Surveyor: Iron.

R.E. Burris, LCRC Liber 1, Page 311, July 19, 1973: Found 1/2" iron rod.

This corner is the N.W. corner of Lot 10 of Litchfield Industrial Park.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x18" iron rod. Replaced with 3/4"x36" County remonumentation bar and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar
 In E/W fence line, 5' East of fence to South
 Found nail & spotter RLS #25832 N. side 24" Maple stump, West 4.08'
 Found nail & spotter RLS #25832 W. side 24" Oak South 6.13'
 Nail in S. side 12" Ash East 23.27'
 Nail in N.W. side 14" Ash, S. 40° W., 26.78'



Signed by Frederick J. Cutcher

Date November 27, 1994

Surveyor's Michigan License No. 24592