

RECORDED

HILLSDALE CO. MICH.

97396

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

'94 NOV 28 AM 11 08

Filing Requirement of Act 74, Mich. P.A. 1970



For corners in

Hillsdale

(County)

Located In:

Corner Code #

Judy VanZandt
REG. OF DEEDS

1. Public Land Survey

T 5S R 4W

G-7

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. , Recorded Plat

5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. Cutcher, in a field survey on October 20, 1994


do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A. Kurzy, LCRC Liber 1, Page 241, Dec. 26, 1972: Found iron 6" below surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 10" long iron bar in monument box in centerline of E/W road, and in line with fences N. & S. Replaced with 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4"x36" County remonumentation bar in monument box
In centerline E/W road in line with fences N. & S.
N.E. corner of 2' square fence post S. 31.15'
Nail & Spotter in E. side R. R. tie brace post N. 12° W., 34.51'
Nail & Spotter in S.W. side 30" Oak S. 60° E., 62.43'
Nail & Spotter in S.E. Side 24" Cherry N. 60° E., 53.75'



Signed by Frederick J. Cutcher
24592

Date November 15, 1994

Surveyor's Michigan License No.