

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1999-05 MEETING HELD ON AL RINGENBERG, CO. DEED

99 SEP -2 AM 9:16

HILLSDALE COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

July VanJanet
REG. OF DEEDS

For corners in

HILLSDALE Located In: Corner Code #
(County)
LITCHFIELD TWP.

- 1. Public Land Survey T5S R4 W G-13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. Cutcher, in a field survey on July 22, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O., 2/3/1825, John Mullett: W. Ash 24" N 71° E. 64; W. Oak 10" N. 12 1/2° W. 18.

Survey No. 1108, 12/16/1889, R.J. Coryell: Stone and brick said to have been set by Bullard (no references).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No remaining references. Stone not found. Set corner GLO distance of 10 lks. (6.6') West of G-1 Allen Township.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" diameter iron with County Remonumentation Cap in monument box and is accepted as the best available evidence of the position of the original corner.

6.6' West of G-1 Allen Township and centerline of M-49; in centerline with Jonesville Road; cor. conc. curb N. 5° W. 76.37'; nail & spotter 18" Spruce S. 19° W. 75.0'; cor. conc. curb S. 10° W. 76.77'; found p.k. util. pole S. 42° E. 48.48';



Signed by *Frederick J. Cutcher*
Surveyor's Michigan License No. 24592

Date 7/30/99