



LIBER 3 PAGE 56 97397

RECORDED HILLSDALE CO. MICH.

'94 NOV 28 AM 11 08

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in

Hillsdale (County)

Located In:

Corner Code #

1. Public Land Survey

T 5S. R 4W.

H-3

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

SURVEY & REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

4. Lot No. , Recorded Plat

5. Private Claims

Grid with columns A-M and rows 2-13. A dot is marked at the intersection of column H and row 3.

I, Frederick J. Cutcher, in a field survey on July 25, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A. J. Hatt, LCRC Liber 1, Page 189, Sept. 21, 1972, found R.R. spike in pavement from T. Kurzy's witnesses of November, 1970.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike at road surface. Found 1/2" iron rod below R.R. spike. Found iron pipe below 1/2 iron rod. Top of iron pipe is 1.7' below road surface. Broke off iron rod and set 3/4" x 36" Co. remonumentation bar in monument box beside iron pipe with top of iron over pipe in place of R.R. spike and 1/2" iron rod. This corner has been used on many suveys and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar in monumnt box In centerline E/W road, 1.7' W. of centerline N/S road Nail in S.W. side 24" Maple N. 57° E., 55.93' Nail in N. side street light post S. 38° W., 35.88' Nail in W. side 24" Maple S. 13° E., 83.70' Nail in N.E. side 18" Maple N. 67° W., 79.00' S.E. corner house #1100 N. 45° W., 116.45' Nail & spotter in N.W. side utility pole S. 50° W., 46.60'



Signed by Frederick J. Cutcher

Date October 12, 1994

Surveyor's Michigan License No. 24592