

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT MEETING HELD ON 1-10-94 AL RINGENBERG, CO. REC.

LIBER 3 PAGE 59 **97400**

RECORDED HILLSDALE CO. MICH.

REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 09

*Judy VanZandt*  
 REG. OF DEEDS

For corners in  
Hillsdale  
 (County)

Located In: Corner Code #

- 1. Public Land Survey T 5S R 4W H-5
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

**SURVEY & REMONUMENTATION**

APR 27 1995

Register of Deeds Stamp & File Number  
**COMMISSION**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5							●					
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Frederick J. Cutcher, in a field survey on October 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Survey #1173, July 2, 1894, Geo. Mark, Co. Surveyor: Iron stake.

A. Kurzy, LCRC Liber 1, Page 243, Dec. 26, 1972: Fd. 3/4" iron center Chicago Street & St. Joe Street.

M. Mahieu, LCRC Liber 716, Page 627, Oct. 17, 1994: Fd. 1" iron pipe in monument box at intersection S. Chicago & West St. Joe Street.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron pipe 28" long in monument box in centerline interstections of St. Joe and Chicago Streets. Dug layer of asphalt around monument box. Monument box is concreted in and could not remove. Replaced iron pipe with 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4"x36" County remonumentation bar in monument box
- In centerline intersections of St. Joe and Chicago Streets
- Top center Fed. Aid Project marker (R.O.W. marker) N. 54° E., 54.78'
- Top center fire hydrant N. 50° W., 41.91'
- N.W. corner building S. 36° E., 47.72'
- Center manhole cover S. 53° E., 17.43'
- Center manhole cover N. 65° W., 32.0'



Signed by Frederick J. Cutcher

Date November 15, 1994

Surveyor's Michigan License No. 24592