

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-10-94 AL RINGENBERG, CO. R.R.

LIBER 3 PAGE 61 97402

RECORDED HILLSDALE CO. MICH. '94 NOV 28 AM 11 09

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Hillsdale (County)

Located In: Corner Code --#

- 1. Public Land Survey T 5S. R 4W. I-3
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

Julie VanZandt REG. OF DEEDS

SURVEY & REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number COMMISSION

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Frederick J. Cutcher, in a field survey on October 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


R. E. Burris, LCRC Liber 1, Page 395, Apr. 19, 1974, found P.K. nail in road. Dug under nail, could not find evidence of original corner. Set R.R. spike in place of P.K. nail and witnessed.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike in centerline intersection of roads. Dug down 24"± to natural ground, found nothing else. Replaced R.R. spike with 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4"x36" County remonumentation bar in monument box
- In centerline intersection of roads
- P.K. in W. side power pole S. 25° W., 89.00'
- P.K. in W. side 36" Maple N. 15° E., 76.17'
- Top center telephone stanchion N. 35° W., 37.58'
- S.W. corner brick house N. 50° W., 189.53'



Signed by Frederick J. Cutcher 24592

Date October 12, 1994

Surveyor's Michigan License No.