

'94 NOV 28 AM 11 09

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990 AT A MEETING HELD ON 10-94 AL RINGENBERG, CO. REC

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in

Hillsdale

(County)

Located in:

Corner Code #

1. Public Land Survey

T 5S R 4W

1-5

T R

T R

T R

S T R

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

I, Frederick J. Cutcher, in a field survey on October 4, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey #1162, July 14, 1894, Geo. Mark, Co. Surveyor: Stone & brick; W. Oak stump S. 57 1/2° E., 116 links.

C.D. Plye, R.L.S. #3165 found pointed stone surrounded by broken brick and china 2' below surface. Reset 1" iron pipe over stone 4" below surface. A. Kurzy, Dec. 1970 found iron rod, according to LCRC Liber 1, Page 57, Nov. 12, 1971, by A.J. Hatt.

A. J. Hatt, LCRC Liber 1, Page 57, Nov. 12, 1971: set P.K. in pavement.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1"x5" iron pipe over stone. Top of iron pipe was 4" below pavement surface. Top of stone was 1.2' below pavement. Good deposit of brick & china was found around stone. Removed stone and replaced with 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar in monument box

In centerline of intersection of streets.

Center manhole cover West 27.06'

S.W. corner house foundation N. 45° E., 74.45'

Top center triangular concrete post S. 50° E., 42.32'

Top fire hydrant S. 50° W., 35.17'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Frederick J. Cutcher

Date November 15, 1994

Surveyor's Michigan License No. 24592