



LIBER 3 PAGE 63

97404

RECORDED

HILLSDALE CO. MICH.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 09

For corners in

Hillsdale
(County)

Located In:

Corner Code #

Judy VanZandt
REG. OF DEEDS

- 1. Public Land Survey T 5S R 4W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

SURVEY &
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number
COMMISSION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Frederick J. Cutcher, in a field survey on October 26, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E.R. Reed, LCRC Liber 1, Page 608, Oct. 9, 1979: Found pieces of coal, pile of stones agreeing with fencelines. Set a cast iron Harrison marker.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Harrison monument at road surface. Replaced Harrison with 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4"x36" County remonumentation bar in monument box
- In centerline E/W road and 1' East of fence running North
- N.W. corner house foundation S. 58° E., 177.85'
- N.E. corner barn S. 45° W., 109.50'
- N. corner telephone stanchion S. 20° E., 56.53'
- Nail & spotter in S. side of 24" Maple N. 75° E., 76.28'



Signed by Frederick J. Cutcher

Date November 15, 1994

Surveyor's Michigan License No. 24592