

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980. MEETING HELD ON 10/23/97 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 234
REMONUMENTATION

128735

RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

For corners in

HILLSDALE
(County)

Located In:

Corner Code ##

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>6S</u> R <u>1W</u> | <u>A-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Jeffrey A. Bieszk
REG. OF DEEDS

**SURVEY &
REMONUMENTATION**

FEB 11 1998

Register of Deeds Stamp & File Number

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)
30" Beech S 76 E 23 lks
6" Beech N 14 W 16 lks
26 lks South M-5, T6S-R2W

County Survey (George Marks No. 817)
found stone no witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no iron at location, found iron for M-5, Township 6 South, Range 2 West, dug at the falling and found nothing set corner at falling. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail w/tag fence post N 07 E 21.78 ft.
Nail w/tag 8" Box Elder S 75 E 50.92 ft.
Nail w/tag 4" Box Elder S 40 E 50.23 ft.
Stop sign post S 32 E 53.56 ft.



Signed by *Jeffrey A. Bieszk*

Date 25 November 1997

Surveyor's Michigan License No. 41093