



LIBER 3 PAGE 235
REMONUMENTATION

128736 RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

Jeffrey A. Bieszk
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

Register of Deeds SECTION File Number

For corners in

HILLSDALE
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 6S R 1W B-5
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	•												
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)	County Survey (George Marks No. 817)
7" Elm S 86 E 10 lks	Reestablished, stake
13" Elm S 66 W 12 lks	30" Beech S 34 E 20.75 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no iron at location, dug at location established from single proportionate from A-5 and C-5. Found nothing, set corner from single proportionate measurement being 2.5 feet West fence to the South. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box		
center steel fence post	S 05 E	31.91 ft.
Nail w/tag 18" Elm	S 05 W	71.79 ft.
Nail w/tag 4" Elm	S 77 E	132.27 ft.
Nail w/tag 4" Elm	N 80 E	137.12 ft.



Signed by *Jeffrey A. Bieszk* Date 25 November 1997
Surveyor's Michigan License No. 41093