

ACCEPTED BY THE HILLSDALE CO. SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1890 AT A MEETING HELD ON 12/10/97
AL RINGENBERG, CO. REP.

LIBER. 3 PAGE 237
 REMONUMENTATION

128738

RECORDED

HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

97 NOV 26 PM 4 08

For corners in

HILLSDALE
 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>6S</u> R <u>1W</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Judy VanZandt
 REC'D DEEDS

SURVEY &
 REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number
 SECTION

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)
 6" Beech S 10 E 7 lks
 7" Ironwood N 42 E 19 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" rebar 36", long in the centerline of Hoxie Road and 1 foot East of occupation to the North. Dug under iron and found stone reset iron over stone. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
 Nail w/tag R.R. Tie Post N 05 W 25.25 ft.
 Nail w/tag 6" Elm N 60 W 54.23 ft.
 Mail box post S 55 W 31.29 ft.
 Nail w/tag Power Pole S 50 E 35.58 ft.



Signed by [Signature]

Date 25 November 1997

Surveyor's Michigan License No. 41093