

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1997 AT A MEETING HELD ON 11/12/97 AT AL RINGENBERG CO. REP.

LIBER 3 PAGE 222  
REMONUMENTATION

128723

RECORDED  
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 07

*Justy Vanjandt*  
REG. OF DEEDS

SURVEY &  
REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number  
SECTION

For corners in

HILLSDALE  
(County)

Located In:

Corner Code ##

- |                                       |                         |            |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey                 | T <u>6S</u> R <u>1W</u> | <u>G-1</u> |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
|                                       | T _____ R _____         | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____      |
|                                       | S _____ T _____ R _____ | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                         |            |
| 5. Private Claims _____               |                         |            |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)  
36" W. Oak S 37 W 8 lks  
6" W. Oak N 70 E 3 lks  
42 lks West G-13 T5S-R1W

LCRC by Kenneth L. Suydam  
Set R.R. Spike  
Cen. 6" Steel post N 05 W 31.67 ft.  
Face R.R. tie post S 60 E 52.40 ft.  
Face Wood post S 45 W 35.90 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In LCRC by Suydam, found nothing set corner by pro-ration of fences from West and line from South. I found Corner as witnessed by Suydam, dug and found nothing, accepted as the best available evidence of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box		
Fence Post w/ tag	S 45 W	36.15 ft.
Fence Post w/tag	S 55 E	52.65 ft.
Stop sign	N 75 E	70.14 ft.
Phone Box	N 15 W	33.42 ft.



Signed by *Jeffrey A. Bieszk*  
Surveyor's Michigan License No. 41093

Date 25 November 1997