

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-20-90 AL RINGENBERG, CO. REC.

LIBER 3 PAGE 223 **128724** RECORDED
 REMONUMENTATION HILLSDALE CO. MICH.
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 **87 NOV 26 PM 4 07**

For corners in

HILLSDALE
 (County)

Located In:

Corner Code #/

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>6S</u> R <u>1W</u> | <u>G-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Janet VanZandt
 REG. OF DEEDS
SURVEY & REMONUMENTATION
FEB 11 1998
 SECTION _____
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)	LCRC by Kenneth L. Suydam
8" Beech S 69 E 19 lks	Set R.R. Spike
8" Beech S 63 W 19 lks	Nail and Washer 10" Ash N 85 W 33.24 ft.
	Fence Post East 31.85 ft.
	Nail and Washer 20" Maple S 35 E 52.85 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In LCRC by Suydam, found nothing set corner in line with East-West and split fences I found Corner as witnessed by Suydam, dug and found nothing, accepted as the best available evidence of the position of the original Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box		
Nail w/tag 14" Walnut	N 85 W	33.50 ft.
Nail w/tag 14" Hickory	S 55 W	34.66 ft.
Nail w/tag R.R. tie post	East	32.10 ft.
Nail w/tag 18" Walnut	S 45 E	41.60 ft.



Signed by *Jeffrey A. Bieszk*
 Surveyor's Michigan License No. 41093

Date 25 November 1997