

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON 10-30-97 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 226
REMONUMENTATION

128727 RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE '97 NOV 26 PM 4 07
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>6S</u> R <u>1W</u> | <u>G-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Janey VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number
SECTION

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)
6" Ironwood S 25 E 25 lks
6" Ironwood S 70.5 W 27 lks

County Survey (George Marks 1901)
Stone

LCRC (Maurice H. Mahieu L 604, P 623)
Nail 10" Oak S 85 W 26.60 ft.
Nail 24" Elm N 25 W 71.23 ft.
Nail 18" Ash N 15 E 86.23 ft.
Nail 15" Maple N 80 E 46.09 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Mahieu found 1/2" rod in centerline of Waldron Road and extension of trees West. Excavated area with backhoe to a size of 6 ft. by 8 ft. by 3.5 ft. deep. Found large pointed stone and accepted same as corner. He set a Harrison Monument over stone. Corner was 5.5 feet West of centerline and in line with trees West. I found Harrison Monument and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail w/tag 16" Oak S 85 W 26.60 ft.
Nail w/tag 18" Oak N 50 W 43.28 ft.
Nail w/tag 10" Maple N 80 E 32.45 ft.
Nail w/tag 18" Oak S 75 W 33.23 ft.



Signed by *[Signature]*

Date 25 November 1997

Surveyor's Michigan License No. 41093