

ACCEPTED BY THE HILLSDALE SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 344 OF 1990 AT 77A MEETING HELD ON 11/12/97 AL RINGENBERG, CO. REP.

LIBER 3 PAGE 227
REMONUMENTATION

128728

RECORDED
HILLSDALE CO. MICH.

'97 NOV 26 PM 4 07

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Jeffrey A. Bieszk
REC. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number
SECTION

For corners in

HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6S</u> R <u>1W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)
12" Hickory N 86 E 14 lks
5" Ironwood S 51 W 21 lks

LCRC (Maurice H. Mahieu L 604, P 624)
Nail 24" Walnut S 12 E 110.30 ft.
Nail Utility Pole S 13 W 178.83 ft.
Nail 12" Walnut S 88 W 41.88 ft.
Nail R.R. tie fence post N 84 E 29.89 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Mahieu found 1/2" rod in centerline of Road. Rod was used by other area surveyors. He accepted iron. I found iron as witnessed by Mahieu, dug under iron found nothing, and accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail w/tag fence post N 87 E 29.73 ft.
Nail w/tag Twin Hickory N 12 E 118.00 ft.
Nail w/tag 14" Walnut S 85 W 42.12 ft.
Nail w/tag 22" Walnut S 10 E 110.65 ft.



Signed by *[Signature]*

Date 25 November 1997

Surveyor's Michigan License No. 41093