

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON _____ AL RINGENBERG CO. REP.

LIBER 3 PAGE 228
REMONUMENTATION

128729 RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

Judy VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

Register of Deeds, Stamp & File Number
SECTION

For corners in

	HILLSDALE (County)	Located In:	Corner Code #
1. Public Land Survey		T <u>6S</u> R <u>1W</u>	<u>G-8</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____	T _____ R _____	_____
	S _____	T _____ R _____	_____

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Jeffrey A. Bieszk, in a field survey on 12 November, 1997

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- GLO set by Robert Clark Jr. (1824)
- 5" Beech N 27 E 10 lks
- 4" Ironwood S 21.5 E 18 lks

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. Spike in centerline of Road and occupation to the West. Dug under R.R. spike and found nothing. There was no other information on said corner. Accepted as the Best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- Nail w/tag 6" Poplar S 85 W 33.40 ft.
- Nail w/tag 18" Stump N 82 E 37.08 ft.
- Nail w/tag Twin Poplar N 12 E 149.90 ft.
- Phone Box S 25 E 74.05 ft.



By *[Signature]*

Date 25 November 1997

Surveyor's Michigan License No. 41093