

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990. MEETING HELD ON [Signature] AL RINGENBERG, CO. REP.

LIBER 3 PAGE 229
REMONUMENTATION

128730 RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

Jeffrey VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number

For corners in

HILLSDALE
(County)

Located In: Corner Code #

- 1. Public Land Survey T 6S R 1W G-9
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jeffrey A. Bieszk, in a field survey on 12 November, 19 97,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO set by Robert Clark Jr. (1824)
- 28" W. Ash N 20 W 4 lks
- 6" Sycamore S 74 E 18 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron with ribbon and had a flat chisel like end. Dug under iron and found nothing. Said iron was in the centerline of Waldron Road and Church Road. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- Nail w/tag Power Pole S 30 W 59.30 ft.
- Nail w/tag 28" Maple N 50 W 59.46 ft.
- Center of conc. R.O.W marker N 40 W 51.45 ft.
- Nail w/tag 18" Maple N 40 E 61.97 ft.



Signed by *[Signature]* Date 25 November 1997
Surveyor's Michigan License No. 41093