

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1993 AT A MEETING HELD ON 12/1/97 AT AL RINGENBERG, CO. REP.

128731 RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 230
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE '97 NOV 26 PM 4 08
Filing Requirement of Act 74, Mich. P.A. 1970

Jeffrey VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number
SECTION

For corners in

HILLSDALE
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6S</u> R <u>1W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jeffrey A. Bieszka, in a field survey on 12 November, 1997

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO set by Robert Clark Jr. (1824)
- 6" Ironwood S 16 E 12 lks
- 5" Beech N 19 W 3 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike in centerline of Waldron Road and 1 foot South of fence line to the West and in line with tree line to the East. Dug under R.R. spike and found nothing, there was no other information to said corner. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- Nail w/tag 12" Hickory S 85 E 23.34 ft.
- Nail w/tag Multiple Poplar S 45 E 34.43 ft.
- Nail w/tag 28" Walnut N. 75 W 37.77 ft.
- Nail w/tag Twin Hickory West 34.63 ft.



Signed by [Signature] Date 25 November 1997
Surveyor's Michigan License No. 41093